


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

15-095-01642-0001
 15095-01642001

RB

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
 Section Plat

Kingman County. Sec. 13 Twp. 27 Rge. 10 (E) W (W)
 Location as "NE/CNW/SW" or footage from lines SE SW SW
 Lease Owner Morgenstern & Spector
 Lease Name McMichaels #6 Well No.
 Office Address Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) oil
 Date well completed ~~xxxxx~~ 7-2-51 19
 Application for plugging filed Nov. 10, 1959 19
 Application for plugging approved Nov. 12, 1959 19
 Plugging commenced 12-9-59 19
 Plugging completed 12-11-59 19
 Reason for abandonment of well or producing formation failure to produce
 profitably

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample
 Producing formation Viola Depth to top 4278 Bottom 4281 Total Depth of Well 4282 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8"	294	none
				5-1/2"		3116'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4302' and found it open.
 Filled w/sand to 4275' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.
 Cleared hole and mudded the hole to 220', set 10' rock bridge and dumped 20 sacks of cement.
 Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
 STATE CORPORATION COMMISSION

JAN 19 1960

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Knight Casing Pulling Co. CONSERVATION DIVISION
 Address Chase, Kansas Wichita, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
 I, Noel J. Knight (employee of owner) or (owner/oper) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel J. Knight*
 Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 59

My commission expires 9-27-62 *Thomas J. Doy* Notary Public.



WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15095-016420001

Company - LION OIL CO.
Farm - McMichael No. 6

SEC. 13 T. 27 R. 10W
SE SW SW

Total Depth. 4282
Comm. 6-21-51 Comp. 7-2-51
Shot or Treated.
Contractor. The R. W. Rine Drlg. Co.
Issued. 9-22-51

County. Kingman
KANSAS



Elevation. 1744

Production. BHB Pot. 7620 BOPD

Figures Indicate Bottom of Formations.

soil, sand, redbed	300
red bed, shale	750
shale, shells	1320
lime, shale	1475
shale, shells	1637
lime, shale	2045
shale, shells	2258
shale	2440
shale, lime	2657
salt, lime, shale	2781
shale, lime	3352
lime, shale, sand	3615
lime, shale	3692
lime	3975
lime, shale	4023
lime, chert	4065
chat, chert	4069
shale	4280
lime	4282
Total depth	

Tops:	
Lansing	3501
Mississippi	4021
Viola	4278

500 acid

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1959

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1/14/60

INV. NO. 699-a