


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

R
R

15-095-01591000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 13 Twp. 27 Rge. 10 (E) W (W)
Location as "NE/CNW/SW" or footage from lines: NW SE SW
Lease Owner: Morgenstern & Spector
Lease Name: McMichaels "A" #3 Well No. _____
Office Address: Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole): oil
Date well completed: 6-6-51 19_____
Application for plugging filed: Nov. 10, 1959 19_____
Application for plugging approved: Nov. 12, 1959 19_____
Plugging commenced: 11-23-59 19_____
Plugging completed: 11-27-59 19_____
Reason for abandonment of well or producing formation: failure to produce profitably
If a producing well is abandoned, date of last production: 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Fred Hampel
Producing formation: Viola Depth to top: 4280 Bottom: 4284 Total Depth of Well: 4289 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286'	none
				5-1/2"	4281'	3075'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4289' and found it open.
Filled w/sand to 4270' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.
Cleared hole and checked mud to 260', set rock bridge to 250' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETED

JAN 19 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Knight Casing Pulling Co.
Address: Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or ~~owner~~ operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of December, 19 59

My commission expires 9-28-62

Thomas L. Buggs
Notary Public.



WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas


15-095-01591-0000

Company - LION OIL CO.
 Farm - McMichael No. 3

SEC. 13 T. 27 R. 10W
 N. 7 S. 27 W.

Total Depth. 4284
 Comm. 5-23-51 Comp. 6-6-51
 Shot or Treated.
 Contractor. R. W. Rino Drlg.
 Issued. 7-28-51

County. Kingman
 KANSAS



Elevation. 1742

Production. BHB pot, 4956 bbls.

CASING:

8 5/8" 294' com. w/225 sx.
 5 1/2" 4282 com. w/200 sx.

Figures indicate Bottom of Formations.

sand & clay	300
salt & shale	1168
shale & sholls	1515
lime & shale	1647
lime & shale	2175
shale & sholls	2623
lime & shale	3670
lime	4045
chat & chert	4067
chat & shale	4086
shale	4220
shale	4284
Total Depth	

Tops:	
Lansing	3502
Mississippi	4021
Viola	4280

500 acid.

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 4 1959
 CONSERVATION DIVISION
 Wichita, Kansas