


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County. Sec. 13 Twp. 27 Rge. 10 (E) W (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines NW SW SW  
Lease Owner Morgenstern & Spector  
Lease Name McMichaels "A" #7 Well No. \_\_\_\_\_  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 7-8-51 19\_\_\_\_\_  
Application for plugging filed Nov. 10, 1959 19\_\_\_\_\_  
Application for plugging approved Nov. 12, 1959 19\_\_\_\_\_  
Plugging commenced 12-6-59 19\_\_\_\_\_  
Plugging completed 12-8-59 19\_\_\_\_\_  
Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation Vival Depth to top 4291 Bottom 4292 1/2 Total Depth of Well 4293 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	297'	none
				5-1/2"	4284'	3202'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 4294' and found it open.  
Filled w/sand to 4270' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.  
Cleared hole and mudded the hole to 260', set rock bridge to 250' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED  
STATE CORPORATION COMMISSION

JAN 19 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 1959

My commission expires 9-27-62

Thomas V. Dwyer  
Notary Public.



WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas


COPY  
 15-095-01592-0000

Company - LION OIL CO.  
 Farm - McMichael No. 7

SEC. 13 T. 27 R. 10W  
 NW SW SW

Total Depth. 4294  
 Comm. 6-27-51 Comp. 7-8-51  
 Shot or Treated.  
 Contractor. The R. W. Rine Drilg. Co.  
 Issued. 9-22-51

County. Kingman  
 KANSAS



CASING:  
 9 5/8" 305 cem w/250 sxs.  
 5 1/2" 4292 1/2 cem w/200 sxs.

Elevation. 1755  
 Production. BHB Pot. 3176 BOPD

Figures Indicate Bottom of Formations.

sand	160
red rock, shells	305
red bed, shale, shells	915
shale, shells, salt	1375
lime	1640
lime, shale	1885
shale	3025
lime, shale	3627
lime	4000
lime, chert	4075
shale	4120
lime, shale	4294
Total depth	

Tops:	
Lansing	3515
Mississippi	4022
Viola	4291

750 acid

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 11 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

INVOICED  
 DATE 1/14/60  
 INV. NO. 709-d