


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 13 Twp. 27 Rge. 10 (E)W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Morgenstern & Spector
Lease Name McMichael #8 Well No.
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 8-2-51 19.
Application for plugging filed Nov. 10, 1959 19.
Application for plugging approved Nov. 12, 1959 19.
Plugging commenced 11-24-59 19.
Plugging completed 11-28-59 19.
Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Viola Depth to top 4274 Bottom 4275 Total Depth of Well 4288 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	287'	none
				5-1/2"	4278'	3234'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4288' and found it open.
Filled w/sand to 4260' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.
Cleared hole and checked mud to 260', set rock bridge to 250' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETED

JAN 19 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
K. Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of December, 1959

My commission expires 9-27-62 Notary Public.



WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-095-01593-0000

Company - LION OIL CO.
Farm - McMichael No. 8

SEC. 13 T. 27 R. 10W
NW NW SW

Total Depth. 4290 Corr. to 4288
Comm. 6-27-51 Comp. 7-8-51
Shot or Treated. 500 acid
Contractor. The R. W. Rine Drlg. Co.
Issued: 9-22-51

County. Kingman
KANSAS



CASING:

9 5/8" 295' cem w/250 sxs.
5 1/2" 4284' cem w/200 sxs.

Elevation. 1755

Production. BHB Pot. 1968 BOPD

Figures Indicate Bottom of Formations.

sand	70
sand, clay, redbed	300
sand, red bed	1100
shale, shells	1325
lime, shale	2280
shale	2475
shale, lime	2825
shale	3025
shale, lime	3343
shale	3500
lime	3980
lime, chert	4055
chert	4070
lime	4110
shale	4225
lime, shale	4290
Total depth Corr.	4288

Tops:
Lansing 3508
Mississippi 4018
Viola 4283

RECEIVED
STAT. CORPORATION COMMISSION
DEC 4 1959
CONSERVATION DIVISION
Wichita, Kansas