


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 N. Broadway  
Wichita, Kansas

*P*

15-09501646-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Kingman County. Sec. 13 Twp. 27 Rge. 10 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines NE NE SW  
Lease Owner Morgenstern & Spector  
Lease Name McMichaels #9 Well No. \_\_\_\_\_  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 7-12-51 19\_\_\_\_  
Application for plugging filed Nov. 10, 1959 19\_\_\_\_  
Application for plugging approved Nov. 12, 1959 19\_\_\_\_  
Plugging commenced 11-29-59 19\_\_\_\_  
Plugging completed 12-1-59 19\_\_\_\_  
Reason for abandonment of well or producing formation failure to produce profitably  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation Viola Depth to top 4273 Bottom 4274 Total Depth of Well 4275 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	286'	none
				5-1/2"	4267'	3048'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 4275' and found it open.  
Filled w/sand to 4260' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.  
Cleared hole and checked mud to 300', mudded the hole to 250', set rock bridge to 240' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 27' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED  
STATE CORPORATION COMMISSION

JAN 19 1960

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co. CONSERVATION DIVISION  
Address Chase, Kansas Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE ss.  
I, Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 59

My commission expires 9-27-62

Thomas V. Doyne  
Notary Public.



WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas


15-095-01646-0000

Company - LION OIL CO.  
 Farm - McMichael No. 9

SEC. 13 T. 27 R. 10W  
 NE NE SW

Total Depth. 4279  
 Comm. 7-3-51 Comp. 7-12-51  
 Shot or Treated. 750 acid  
 Contractor. The R. W. Rife Drlg. Co..  
 Issued. 9-22-51

County. Kingman  
 KANSAS



Elevation. 1740

Production. flow pot. 134 BOPD

CASING:

9 5/8" 295' cem w/250 sxs.  
 5 1/2" 4274' cem w/200 sxs.

Figures Indicate Bottom of Formations.

sand, shale, redbed	300
shale	420
red bed, shale, shells	
	1320
lime, shale	2105
shale	2805
lime, shale	3005
shale	3155
shale, lime	3435
shale	3565
lime, shale	4016
lime, chert	4059
shale	4260
shale, lime	4273
lime	4275
lime	4279
Total depth	
Tops:	
Lansing	3486
Mississippi	4008
Viola	4273

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 11 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

INVOICED  
 DATE 1/14/60  
 INV. NO. ~~76-w~~ 704-w