



15-095-17549-0000

FREELAND #1 WELL

LOCATION: SW $\frac{1}{4}$  SW $\frac{1}{4}$  SE $\frac{1}{4}$  Sec. 13-27S-10W  
Kingman County, Kansas

SPUDED: 6-10-51

OPERATOR: Anderson-Prichard Oil Corp.

COMPLETED: 6-25-51

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: Ran 315.93' 8-5/8" 28.55# casing  
cemented at 311' with 275 sacks  
bulk cement and 3 c.c.

OIL STRING: Ran 4268' 5 $\frac{1}{2}$ " 14# casing cemented  
at 4265' with 175 sacks bulk cement.

L O G

(Figures indicate bottom of formation)

|   |    |      |                         |
|---|----|------|-------------------------|
| 0 | to | 140  | Surface and sand        |
|   |    | 170  | Red bed                 |
|   |    | 250  | Shells and red bed      |
|   |    | 315  | Red bed and shale       |
|   |    | 350  | Red bed and shells      |
|   |    | 370  | Shale and shells        |
|   |    | 500  | Red bed and shale       |
|   |    | 620  | Shale, sand and red bed |
|   |    | 635  | Anhydrite               |
|   |    | 1400 | Shale and shells        |
|   |    | 2440 | Lime and shale          |
|   |    | 2605 | Shale                   |
|   |    | 3555 | Lime and shale          |
|   |    | 3775 | Lime                    |
|   |    | 3808 | Lime and shale          |
|   |    | 3845 | Lime                    |
|   |    | 3900 | Shale and lime          |
|   |    | 4065 | Lime                    |
|   |    | 4115 | Shale and lime          |
|   |    | 4170 | Shale                   |
|   |    | 4267 | Shale and lime          |
|   |    | 4267 | Total Depth.            |

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Freeland #1 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery

Subscribed and sworn before me  
this 27th day of June, 1951.

Wissam J. Zinger  
Notary Public

My commission expires November 29, 1954.

**PLUGGING**  
PRK SEC 13 T 27 R 10W  
BOOK PAGE 29 LINE 45