


15-095-30083-0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 5 - 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Lee Phillips & J. C. Graves

Complete Address: 412 Union Center Bldg., Wichita, Kansas

Lease Name Young Well No. # 1

Location NE NE SW Sec. 34 Twp. 27 Rge. 5 (E) (W) W

County Kingman Total Depth 3833'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Graves Drilling Company, Inc.

Address: 412 Union Center Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 2:45PM Day 2nd Month May Year 1966

The Above well was plugged as follows:

203' of 8 5/8" surface pipe, cement circulated with 165 sacks. Hole  
was filled with drilling mud to 190', 1st cementing plug, bridged solid  
with dry cement and 1/2 sack of hulls on fluid at 190', and cemented with  
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,  
bridged solid with dry cement and 1/2 sack of hulls on fluid at 40', and  
cemented with 10 sacks to the base of the cellar. Rat hole bridged and  
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/5/66  
INV. NO. 3168-W

Signed: Audie Elving  
Well Plugging Supervisor