

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-21765-00-00
Spot: NESWSWNW Sec/Twnshp/Rge: 6-33S-6E
2986 feet from S Section Line, 4819 feet from E Section Line
Lease Name: BARKMAN Well #: 2
County: COWLEY Total Vertical Depth: 3170 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1893	1290	75 SX
PROD	4.5	3169		150 SXS CMT
SURF	8.625	170		85 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2016 8:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Revd. from: DWAIN STOUT Company: RRA INC Phone: (316) 640-9072

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 1810 W/5 SXS, CIRC. 350'-0'.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 02/09/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE TAGGED TD @ 1890', SANDED WELL BACK @ 1810'. RIH W/ TBG @ 1810', RRA MIXED & PUMPED 10 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1680'. RIH ON WIRELINE CUT 4 1/2" CASING @ 1290'. LAYED DOWN CASING @ 1100', RRA SWEDGED INTO 4 1/2" CSG & PUMPED 24 BBL GEL TO PLUG TO SURFACE, FINISHED LAYING DOWN 34 JOINTS 4 1/2" CASING. 2-8-2016, RIH W/TBG @ 350', RRA ESTABLISHED CIRCULATION, MIXED & PUMPED 111 SXS CLASS A COMMON TO SURFACE. 2-9-2016, TAGGED CEMENT PLUG @ 93', RIH W/ TBG @ 90', RRA ESTABLISHED CIRCULATION, MIXED & PUMPED 33 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. P&A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
1863	1866	CSG	

Remarks: PBTD 1893' / COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 24 2016 Form CP-2/3
CONSERVATION DIVISION
WICHITA, KS
4-6-16

1/4