

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-21147-00-00
Spot: NESWNE Sec/Twnshp/Rge: 6-33S-6E
3680 feet from S Section Line, 1660 feet from E Section Line
Lease Name: CRAIG A Well #: 1
County: COWLEY Total Vertical Depth: 3130 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3126	1781	75 SX
PROD	4.5	3127		75 SXS CMT
SURF	8.63	165		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/17/2016 8:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: DWAIN STOUT Company: RRA INC. Phone: (316) 640-9072

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 2720 W/4 SXS, CIRC. 350'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/22/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE TAGGED TD @ 2790'. SANDED WELL BACK @ 2720'. RIH W/TBG @ 2710', RRA MIXED & PUMPED 10 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 2598'. RIH ON WIRELINE CUT 4 1/2" CASING @ 1781', LAYED DOWN CASING @ 1600', RRA SWEDGED INTO 4 1/2" CSG & PUMPED 24 BBL GEL TO PLUG TO SURFACE, FINISHED LAYING DOWN 51 JOINTS 4 1/2" CASING. 2-22-2016, RIH W/ TBG @ 400', SWEDGED INTO TBG & PUMPED 3 SX GEL SPACER. RIH W/TBG @ 350', RRA ESTABLISHED CIRCULATION, MIXED & PUMPED 135 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCUALTED. P&A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2772	2786	CSG	

Remarks: COMPLIANCE / 10 YEAR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

JK

Received
KANSAS CORPORATION COMMISSION
Form CP-2/3
MAR 24 2016
CONSERVATION DIVISION
WICHITA, KS

720
4-6-16