

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-21172-00-00  
Spot: NENWSWNE Sec/Twnshp/Rge: 34-17S-10W  
3937 feet from S Section Line, 2248 feet from E Section Line  
Lease Name: SCHROEDER MAES Well #: 11X-34  
County: ELLSWORTH Total Vertical Depth: 3399 feet

Operator License No.: 33770  
Op Name: ARES ENERGY, LTD  
Address: 405 N. MARIENFELD SUITE 250  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3285		
CIBP	5.5	3322	1490	
PROD	5.5	3399		125 SX
SURF	8.625	423		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2016 9:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: KEVIN WILSON Company: ARES ENERGY, LTD Phone: (620) 388-2332

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/01/2016 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG PBTD. SET CIBP AT 3285' AND CAP WITH 2-3 SX'S CEMENT. SHOOT CASING OFF AT 1490', PULL TO 1325' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. PULL CASING ON UP AND WAIT 1.5 HRS. TAG CEMENT AT 1160'. PUMP 35 SX'S 60-40 POZ, 4% GEL AT 950', PULL CASING TO 470' AND CIRCUALTE 60-40 POZ, 4% GEL CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF. CAME BACK ON 3-2-16 AND TOPPED OFF WITH 2 CU YARDS OF SLURRY MIX.

Perfs:

Top	Bot	Thru	Comments
3327	3337	CSG	
3309	3315	CSG	
3304	3312	CSG	

Remarks: DENIED TA WELL. GEMINI WIRELINE #2230. BASIC SERVICES CEMENT #12889. GREAT BEND REDI-MIX TICKET #48605 ON 3-2-2016.

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICAL)  
KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3