

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21914-01-00
Spot: NWNEENE Sec/Twnshp/Rge: 11-35S-8W
154 feet from N Section Line, 649 feet from E Section Line
Lease Name: LIT TRUST 3508 Well #: 2-14H
County: HARPER Total Vertical Depth: 5472 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		10 sx cement
	II 7	5472		320 sx cement
PROD	4.5	5334		0 SX
SURF	9.625	785		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2016 12:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RON ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-6536

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 03/03/2016 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TUBING STUCK IN HOLE. PUMPED 10 BBL WATER WITH COTTON SEED HULL & FOLLOWED 100 SKS CEMENT DOWN TUBING. LOCKED UP & PRESSURED TO 2500# RAN WIRELINE CHARGE DOWN BACKSIDE OF TUBING TO 1400'. PUMPED 100 SX CEMENT. SHOT HOLE AT 830' & CIRCULATED CEMENT BACK TO SURFACE WITH 275 SXS CEMENT. ALL STRINGS FULL OF CEMENT.


Perfs:

Top	Bot	Thru	Comments
8708	8974	CSG	
8232	8611	CSG	
7922	8156	CSG	
7505	7850	CSG	
7093	7439	CSG	
6647	7026	CSG	
6199	6567	CSG	
5766	6130	CSG	
5386	5690	CSG	
5380	8974	CSG	

*Billed/Invoiced
3609'
720
4-8-16*

Remarks: ORR ENTERPRISES CLASS 'C' CEMENT - TMD = 9081

Plugged through: CSG



District: 02

Signed _____

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3