

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-077-21904-01-00
 Spot: N2N2NWNW Sec/Twnshp/Rge: 16-34S-6W
225 feet from N Section Line, 660 feet from W Section Line
 Lease Name: GARLOW 3406 Well #: 2-16H
 County: HARPER Total Vertical Depth: 4619 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	75		11 sx cement
II	7	5039		310 sx cement
PROD	7	5039	1423	310 SX
PROD	4.5	8900		510 sx cement
SURF	9.625	687		370 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2016 12:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES Phone: (405) 406-5522

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
 Date/Time Plugging Completed: 03/23/2016 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 60 DEGREES OR 4665' WITH TUBING. ONE JOINT OF TUBING WAS LAYED DOWN AND THE CASING WAS CIRCULATED WITH MUD AND THEN 40 SKS OF CEMENT WAS PUMPED ON THE BP. THE CASING WAS RECOVERED AND LAYED DOWN. TUBING WAS RUN TO 1 250', WHERE 50 SKS OF CEMENT WAS SPOTTED. PULLED TUBING TO 740, SPOTTED 50 SKS OF CEMENT. PULLED TUBING TO 250' AND CIRCULATED HOLE FULL USING 85 SKS OF CEMENT:

Perfs:

Top	Bot	Thru	Comments
8519	8781	CSG	
8064	8441	CSG	
7717	8009	CSG	
7379	7664	CSG	
6896	7262	CSG	
6582	6841	CSG	
6242	6454	CSG	
5727	6013	CSG	
5306	5620	CSG	
4898	8781	CSG	

Remarks: ORR ENTERPRISES. CLASS C CEMENT. COMPLIANCE TA. MD = 8903

Plugged through: TBG

District: 02

Signed _____

KCC WICHITA
 (TECHNICIAN)
 APR 05 2016

RECEIVED

*Invoiced
 4284'
 220
 4-8-16*

JK