

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-21677-00-00
Spot: NWNESE Sec/Twnshp/Rge: 4-11S-17W
1980 feet from S Section Line, 990 feet from E Section Line
Lease Name: ROY CARMICHAEL Well #: 4
County: ELLIS Total Vertical Depth: 3482 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2255 S WADSWORTH BLVD, STE 205
LAKEWOOD, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3481		150 SX
SURF	8.625	206		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2016 8:30 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: JOHN CEARLEY AND JOHN Company: VENTURE RESOURCES, INC. Phone: (785) 731-5073

Proposed Plugging Method: Ordered 285 sx 60/40 pozmix 4% gel cement, 12 sx gel and 500 # hulls.
Squeezed Dakota at 640' on Aug 1st 1985 w/200 sx light cement and 75 sx quick set cement. Perforations: Congl - 3403' - 3414' OA

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2016 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

LK Wireline perforated at 1650' and 1147'. Chito's ran in hole with tubing to 3300'. Swift rigged to tubing and pumped 13 sx gel followed by 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1650'. Swift rigged to tubing and pumped 145 sx cement w/250 # hulls mixed in to circulate cement to surface. Pulled tubing. Topped off 5 1/2' casing w/25 sx cement. Hole standing full. Riggged to 8 5/8" casing with instant pressure. Blew cement out top of head.

GPS: 39.12417 -099.20692

Perfs:

Top	Bot	Thru	Comments
3403	3414		

Remarks: SWIFT SERVICES TICKET # 28830

Plugged through: TBG

District: 04

Signed



KCC WICHITA

(TECHNICIAN)

CM

APR 08 2016

Form CP-2/3

APR 01 2016

RECEIVED

220
4-8-16