

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22168-00-00
Spot: SENESE Sec/Twnshp/Rge: 4-11S-17W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: ROY CARMICHAEL Well #: 6
County: ELLIS Total Vertical Depth: 3427 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2255 S WADSWORTH BLVD, STE 205
LAKEWOOD, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3425		150 SX
SURF	8.625	269		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2016 8:30 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: JOHN COARLEY Company: VENTURE RESOURCES, INC. Phone: (785) 731-5073

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix 4% gel cement, 7 sx gel and 500 # hulls.
Perforations: 3362' - 3382' Marm.
Squeezes: 1035' w/250 sx cement.
Squeezed in 2012: 2050' - 2250' w/200 sx cement, 2317' - 2349' w/200 sx cement, 1224' - 1598' w/200 sx cement.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2016 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Chito's ran in hole with tubing to 3300'. Swift rigged to tubing and pumped 7 sx gel followed by 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1650'. Rigged to tubing and pumped 105 sx cement w/250 # hulls mixed in to circulate cement to surface. Pulled tubing and topped off 4 1/2" casing with 20 sx cement. Hole standing full. Rigged to 8 5/8" casing. Casing was full from previous squeezes.

GPS: 39.12227 -099.20494

Perfs:


Top	Bot	Thru	Comments
3362	3382		

Remarks: SWIFT CEMENTING SERVICES TICKET # 28832

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

C.M

KCC WICHITA

APR 08 2016

RECEIVED

Form CP-2/3

no
4-8-16