

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-19037-00-00
Spot: NWSENE Sec/Twnshp/Rge: 6-14S-19W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: IRVIN Well #: 3
County: ELLIS Total Vertical Depth: 3900 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3878		100 SX
SURF	8.625	211		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2016 11:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: CRAIG HERTEL Company: MURFIN DRILLING Phone: (785) 623-0123

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Squeezed: 607' - 798', 662' - 694', 607' - 798', 815' - 835', 921' - 1043', 1005' - 1037', 1098' - 1129', 1100' - 1191', 1404' - 1440', 1801' - 1956', 1999' - 2029', 2004' - 2036'.
PBTD: 3988'
Perforations: 3531' - 3535', 3582' - 3585', 3679' - 3681', 3704' - 3706', 3729' - 3731', 3752' - 3754'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2016 5:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 2050', 1561' and 850'. Hurricane Services ran in hole with tubing to 3496'. Rigged to tubing and pumped 145 sx cement w/400 # hulls mixed in. Pulled tubing to 2047' and pumped 235 sx cement w/300 # hulls mixed in to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing and pumped 25 sx cement w/325 psi. Shut in pressure 325 psi. Rigged to 8 5/8" casing and pumped 5 sx cement w/300 psi. Shut in pressure 300 psi.

GPS: 38.86629 -099.46974

Perfs:

Top	Bot	Thru	Comments
3752	3754		
3729	3731		
3704	3706		
3679	3681		
3582	3585		
3531	3535		

Remarks: HURRICANE SERVICES TICKET # 100631

Plugged through: TBG

District: 04

Signed _____

KCC WICHITA

(TECHNICIAN)

CM

APR 08 2016

MAR 24 2016

RECEIVED

Form CP-2/3

no 4-8-16