

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24835-00-00
Spot: SESESE Sec/Twnshp/Rge: 31-13S-19W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: RIEDEL, GUS Well #: 15
County: ELLIS Total Vertical Depth: 4020 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4016		150 SX
SURF	8.625	311		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2016 12:15 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: CRAIG HERTEL Company: MURFIN DRILLING CO Phone: (785) 623-0123

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 700 # hulls and 14 sx gel.
PC at 1607' w/340 sx cement.
PBTD - 3988'.
Perforations: 3756' - 3760', 3887' - 3889', 3899' - 3901', 3906' - 3907', 3909' - 3910', 3910' - 3911', 3910 - 3912'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2016 2:45 PM KCC Agent: PAT STAAB

Actual Plugging Report: _____ Perfs: _____

Rigged to 5 1/2" casing with a swedge and pumped 50 sx cement w/400 # hulls mixed in followed by 14 sx gel, followed by 205 sx cement w/300 # hulls mixed in. Pressured to 1000 psi. Shut in pressure 600 psi. Rigged to 8 5/8" casing and pumped 45 sx cement w/300 psi. Shut in pressure 300 psi.
03/23/2016 - Topped off with 10 sx cement. Hole standing full.
GPS: 38.87173 -099.46749

Remarks: HURRICANE CEMENTING CO TICKET # 100629
Plugged through: CSG

District: 04

Signed [Signature] (TECHNICIAN) CM

KCC WICHITA
APR 08 2016
RECEIVED

Form CP-2/3
no
4-8-16

MAR 24 2016