

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26821-00-00
Spot: S2NWSESE Sec/Twnshp/Rge: 25-14S-19W
920 feet from S Section Line, 990 feet from E Section Line
Lease Name: LISA Well #: 1-25
County: ELLIS Total Vertical Depth: 3789 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		150 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/01/2016 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY Witness Type: NONE
Date/Time Plugging Completed: 03/01/2016 3:30 AM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @3690 w/50 sx
2nd plug @1350 w/50 sx
3rd plug @630 w/100 sx
4th plug @275 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx


Perfs:

Remarks: SWIFT

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

APR 08 2016

RECEIVED

MAR 28 2016

Form CP-2/3

NO 4-8-16