

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21158-00-00
Spot: SWNWNWNE Sec/Twnshp/Rge: 21-13S-32W
335 feet from N Section Line, 2480 feet from E Section Line
Lease Name: SCHEETZ Well #: 4-21
County: LOGAN Total Vertical Depth: 4730 feet

Operator License No.: 31217
Op Name: CHACO ENERGY COMPANY
Address: PO BOX 1587
DENVER, CO 80201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4726		665 SX
SURF	8.625	237		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2016 9:30 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: ALAN NELSON Company: CHACO ENERGY CO. Phone: (405) 942-3751

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement and 700 # hulls.
8 5/8" surface casing set at 237' w/165 sx cement.
4 1/2" production casing set at 4726' w/215 sx cement.
Stage Collar set at 2502' w/450 sx cement.
TD 4730'.
Perforations: 4000' - 4631'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2016 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4000' and pumped 140 sx cement w/500 # hulls. Pulled tubing to 2500' and pumped 85-sx cement w/200 # hulls. Pulled tubing to 1250' and pumped 95 sx cement. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" casing and pumped 10 sx cement. Connected to 8 5/8" surface casing and pumped 15 sx cement.

GPS: 38.91544N -100.87971W

Perfs:

Top	Bot	Thru	Comments
4000	4631		

Remarks: CONSOLIDATED OILWELL SERVICES TICKET # 49,665

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

CM

KCC WICHITA

APR 08 2016

RECEIVED

MAR 29 2016

Form CP-2/3

no 4-8-16