

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24608-00-01
Spot: N2NW Sec/Twnshp/Rge: 27-15S-19W
4642 feet from S Section Line, 3947 feet from E Section Line
Lease Name: DINKEL Well #: 3
County: ELLIS Total Vertical Depth: 3401 feet

Operator License No.: 33922
Op Name: MUSTANG ENERGY CORPORATION
Address: PO BOX 1121
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3432	2506	125 SX
SURF	8.625	1219		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2016 7:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: ROD BRIN Company: MUSTANG ENERGY CORP. Phone: (785) 623-0533

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations: 3324' - 3328' - C

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2016 2:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded perforations to 3310'. Pumped 10 sx cement through casing. Shot at 2506'. LK Wireline did 3 point shot casing at 2715'. Didn't come loose. Shot at 2506'. Pulled casing to 1850' and pumped 125 sx cement w/200 # hulls mixed in. Pulled casing to 1240' and pumped 40 sx cement w/100 # hulls. Pulled casing to 900' and pumped 40 sx cement w/100 # hulls. Pulled casing to 450 sx cement w/125 sx cement to circulate cement to surface. Pulled casing. Topped off with 20 sx cement. Hole standing full.

GPS: 38.72386 -099.42664

Perfs:

Top	Bot	Thru	Comments
3324	3328		

Remarks: GLOBAL CEMENTING CO

Plugged through: CSG


District: 04

KCC WICHITA

APR 08 2016

RECEIVED

Signed



(TECHNICIAN)

MAR 24 2016

Form CP-2/3

no
4-8-16