

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-01039-00-01
Spot: NESE Sec/Twnshp/Rge: 14-8S-19W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: HANCE B Well #: 1
County: ROOKS Total Vertical Depth: 3520 feet

Operator License No.: 32287
Op Name: LOST CREEK OIL, INC.
Address: 1225 14 RD
STOCKTON, KS 67669

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3520		0 SX
SURF	8.875	220		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2016 8:30 AM
Plug Co. License No.: 34487 Plug Co. Name: E C & G, LLC DBA JEFF'S OILWELL SUPERVISION
Proposal Rcvd. from: JEFF CRAWFORD Company: E C & G, LLC DBA JEFF'S OILWELL Phone: (785) 885-8013

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/500 # hulls.
CIBP at 3420'
Perforations: 3098' - 3382'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2016 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3367' and pumped 50 sx cement w/75 # hulls. Pulled tubing to 2680' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1293' and pumped 75 sx cement to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/15 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 5 sx cement. Shut in pressure 250 psi.

GPS: 39.35610N -099.40157W

Perfs:

Top	Bot	Thru	Comments
3098	3382		

Remarks: SWIFT SERVICES TICKET # 29114

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

cm

KCC WICHITA

APR 08 2016

RECEIVED

MAR 31 2016

Form CP-2/3

no 4-8-16