

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22264-00-00
Spot: SESESW Sec/Twnshp/Rge: 9-14S-21W
360 feet from S Section Line, 2440 feet from W Section Line
Lease Name: PFEIFER-G Well #: 1
County: TREGO Total Vertical Depth: 4100 feet

Operator License No.: 5252
Op Name: R. P. NIXON OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4099		125 sx
SURF	8.625	225		165 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2016 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DUANE ATCHERBERG Company: R P NIXON OPERATIONS, INC. Phone: (785) 656-0038

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 15 sx gel, 350 # hulls and 5 sx calcium chloride. Port Collar at 1657' w/275 sx cement.
Perforations: 3618' - 3621', 3644' - 3647', 3820' - 3822', 4033' - 4036', 4045' - 4049'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2016 3:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4034' and pumped 100 sx cement w/5 sx calcium chloride and 250 # hulls. Pulled tubing to 2824' and let cement set for 30 minutes. Ran tubing back to 3030' and pumped 12 sx gel followed by 25 sx cement. Pulled tubing to 1711' and pumped 150 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 25 sx cement. Backside is full of cement to surface and would not take any cement.

GPS: 38.84266 -099.66158

Perfs:


Top	Bot	Thru	Comments
4045	4049		
4033	4036		
3644	3647		

Remarks: QUALITY CEMENT TICKET # 1336

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA

APR 08 2016

RECEIVED

APR 8 1 2016

Form CP-2/3

no
4-8-16