

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22215-00-03
Spot: NESWNE Sec/Twnshp/Rge: 9-6S-21W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BEECHER OWWO Well #: 2
County: GRAHAM Total Vertical Depth: 3725 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3723		100 SX
SURF	8.625	250		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2016 12:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 475 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Port Collar at 1812' w/450 sx cement.
Perforations: 3394' - 3398', 3444' - 3447', 3555' - 3569', 3566' - 3569', 3651' - 3656'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2016 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3600' and pumped 75 sx cement w/250 # hulls. Ran tubing to 2910' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2000' and pumped 175 sx cement w/200 # hulls. Good circulation of cement. Pulled tubing and topped off casing w/20 sx cement. Tied on to backside and squeezed w/10 sx cement. Shut in pressure 200 psi.

GPS: 39.54878 -099.66409

Perfs:


Top	Bot	Thru	Comments
3651	3656		
3566	3569		
3555	3569		
3444	3447		
3395	3398		

Remarks: QUALITY CEMENT TICKET # 1524

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA

APR 08 2016

RECEIVED

APR 01 2016

Form CP-2/3

220
4-8-16