

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21187-00-00
Spot: SESESW **Sec/Twnshp/Rge:** 20-23S-10W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: EE YUST **Well #:** 1
County: RENO **Total Vertical Depth:** 3850 feet

Operator License No.: 31958
Op Name: HESSE PETROLEUM CO.,L.L.C.
Address: 400 N WOODLAWN STE 7
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3600		
PROD	5.5	3849	2035	175 SX
SURF	8.625	211		160 SX

Well Type: GAS **UIC Docket No:** **Date/Time to Plug:** 02/24/2016 12:00 PM
Plug Co. License No.: 31925 **Plug Co. Name:** QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY **Company:** **Phone:** (316) 685-4746

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE **WitnessType:** PARTIAL
Date/Time Plugging Completed: 02/24/2016 4:00 PM **KCC Agent:** B. J. HOPE

Actual Plugging Report:

CIBP @ 3600' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2035' PULLED CASING TO 1470', 2/23/16 SPOTTED 35 SX CEMENT. PULLED CASING TO 900' SPOTTED 35 SX CEMENT. PULLED CASING TO 260' CIRCULATED TO SURFACE WITH 110 SX CEMENT. CEMENT FELL BACK TO 180', RIG HAD TO COME BACK ON 2/24/2016, RAN ONE INCH TO 180' CIRCULATED TO SURFACE WITH 80 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3670	3676		
3658	3660		

Remarks: QUALITY WELL SERVICE PROVIDE CLASS A CEMENT FOR THIS PLUGGING. FAILED MIT, PAST TEN YEAR & CASING LEAK.

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

MAR 3 1 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

700
4-7-16

1/8