

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21679-00-00
Spot: E2NWNW Sec/Twnshp/Rge: 31-25S-5E
660 feet from N Section Line, 990 feet from W Section Line
Lease Name: APPLEMAN Well #: 10-A
County: BUTLER Total Vertical Depth: 2556 feet

Operator License No.: 32693
Op Name: HAWKINS OIL, LLC
Address: 427 S BOSTON AVE STE 915
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2423		CAP W/ 4 SKS
PROD	4.5	2553		100 SX
SURF	8.625	217		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2016 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: HUNT HAWKINS Company: HAWKINS OIL LLC Phone: (918) 382-7743

Proposed Plugging Method: CIBP @ 2,423'. 4sx on top. Squeeze shots @ 270' then circ cement from 270 to surface.

Plugging Proposal Received By: JONATHAN HILL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2016 1:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) CORNISH WIRELINE (CHANUTE, KS) RAN IN CIBP ON WIRELINE AND SET AT 2423'. 2) RAN IN W/ DUMP BAILER AND CAPED CIBP W/4 SKS. 3) HOLE LOADED, RAN IN AND PERFORATED AT 270'. 4) RAN IN 9 JOINTS (APPROX. 270') OF TUBING AND ESTABLISHED CIRCULATION. 5) PUMPED 125 SKS OF 60/40 4% CEMENT W/2 % CACL AND CIRCUALTED CEMENT TO SURFACE ON BACKSIDE. 6) BACKSIDE SHUT IN W/ BULL PLUG, CEMENT CIRCUALTED UP 4.5" TO SURFACE. 7) PULLED OUT TUBING AND CEMENT FELL, TOPPED OFF W/ 30 SKS BACK TO SURFACE. CEMENT REMAINED AT SURFACE. 8) WELL CUT DOWN APPROX. 3' AND BURIED.

Perfs:

Top	Bot	Thru	Comments
2473	2480	CSG	

Remarks: CEMENTING COMPLETED BY CONSOLIATED OIL WELL SERVICES, EL DORADO, KS. TICKET #51191.
PLUGGED DUE TO DENIED TA.

Plugged through: TBG

District: 02

Signed

Jonathan Hill

Received
(TRANSPORTER) ON COMMISSION

MAR 31 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

700
4-7-16

1/8