

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21738-00-00
Spot: S2NESW Sec/Twnshp/Rge: 29-31S-9W
1650 feet from S Section Line, 3300 feet from E Section Line
Lease Name: VICKIE JO Well #: 1
County: HARPER Total Vertical Depth: 4951 feet

Operator License No.: 32798
Op Name: HART ENERGIES, LLC
Address: 7122 S SHERIDAN RD STE 2-363
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4916	2845	200 SX
SURF	8.625	230		200 SX
T1	2.875	4402		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/05/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 01/27/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

TRIPPED TUBING TO BOTTOM SPOTTED 60 SX CEMENT WITH 250 LBS OF HULLS, TAGGED AT 4100'. CUT CASING PIPE OFF @ 2845' PULLED CASING TO 1456' SPOTTED 35 SX CEMENT 3% CC + 100 LBS HULLS. PULLED CASING TO 905' SPOTTED 35 SX CEMENT. PULLED CASING TO 350' CIRCUALTED TO SURFACE WITH 110 SX CEMENT.

Perfs:


Top	Bot	Thru	Comments
4742	4748		
4464	4472		

Remarks: QUALITY WELL SERVICE PROVIDED ALL CEMENT FOR JOB - USING CLASS A COMMON CEMENT.

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

MAR 31 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

Handwritten initials and date:
20
4-7-16