

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-00272-00-00
Spot: W2SWNE Sec/Twnshp/Rge: 20-16S-10W
3300 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HAGY Well #: 1
County: ELLSWORTH Total Vertical Depth: 3349 feet

Operator License No.: 30681

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3334		150 SX
SURF	10	305		100 SX

Op Name: HOFFMAN OIL, INC.

Address: 18368 LAWRENCE 2100
MOUNT VERNON, MO 65712

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2016 9:30 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: HOFFMAN OIL, INC. Phone: (620) 786-8744

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/22/2016 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SANDED OPEN HOLE TO 3268' AND CAPPED WITH 10 SX'S CEMENT PUMPED THRU TUBING. PERFORATE AT 1400', 1050', AND 355'. PUMP 35 SX'S COMMON CEMENT WITH 3% CC AND 100#'S COTTON HULLS AT 1400'. PULL TUBING ON UP TO 900' AND WAIT FOR 1 HR. ATTEMPT TO TAG CEMENT - COULD NOT. RUN TUBING BACK DOWN TO 1400' AND PUMPED 50 SX'S COMMON CEMENT WITH 3% CC. PULLED TUBING UP TO 900' AND WAITED 1 HOUR. ATTEMPT TO TAG CEMENT - COULD NOT. DECISION MADE TO COME BACK ON MONDAY & START AGAIN AT 1400'. ON 2-22-2016, RAN TUBING TO 1400' AND PUMPED 50 SX'S COMMON CEMENT WITH CC AND GILSINITE. PULLED TUBING TO 1000' AND WAITED 1.5 HRS. TAGGED CEMENT AT 1200'. RAN TUBING BACK DOWN TO 1050' AND PUMPED 40 SX'S COMMON CEMENT AND 3% CC AND GILSINITE, PULLED TUBING OUT. CONNECTED ON TO CASING AND CIRCULATED 220 SX'S 60-40 POZ, 4% GEL CEMENT TO SURFACE. WAITED AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3334	3349	OH	

Remarks: TA N.O.V. LETTER WAS SENT ON THIS WELL. LOG TECH OF KS #8676. COPELAND TICKET #C-43684 AND C-43685 ON 2-22-2016.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 24 2016 CP-2/3

CONSERVATION DIVISION
WICHITA, KS

Handwritten: 700
4-7-16

Handwritten: ✓ JHC