

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-19453-00-00
Spot: SWSESENE Sec/Twnshp/Rge: 23-10S-18W
2666 feet from S Section Line, 452 feet from E Section Line
Lease Name: SHEPARD Well #: WSW
County: ROOKS Total Vertical Depth: 1112 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	1111		275 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 03/11/2016 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Well Drilled on 07/08/1966. No records found.
7" casing set at 1111' w/275 sx cement to surface.
4 1/2" tubing unknown.
Production perforations: 551' - 743' (Cheyenne)

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 03/11/2016 12:35 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Pulled 1" rods w/3 3/4" plunger on bottom, estimate pump barrel at 535'. Unable to pull 4 1/2" tubing. Perforated 2 holes at 525'. Ran 2 3/8" tubing to 501'. Swift Services pumped 145 sx cement w/300 # hulls. Cement circulated. PTOH. Topped off 4 1/2" tubing w/5 sx cement. Hooked to backside and pumped 20 sx cement. Maximum pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
741	743		
718	732		
618	628		
564	566		
551	552		

Remarks: SWIFT SERVICES TICKET # 29195

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

MAR 15 2016

Received
KANSAS CORPORATION COMMISSION

MAR 22 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

70
4-7-16