

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-159-19056-00-01
 Spot: SWSES Sec/Twnshp/Rge: 6-19S-10W
303 feet from S Section Line, 3735 feet from E Section Line
 Lease Name: KOWALSKY Well #: 5
 County: RICE Total Vertical Depth: 3378 feet

Operator License No.: 31070
 Op Name: EAGLE RIVER ENERGY CORPORATIO
 Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3040		
CIBP	5.5	3295		
PKR		3060		PACKER TYPE AND SETTING DEPTH: SL SHEAR SET AT 3060
PROD	5.5	3378		
SURF	8.625	236		
T1	2.375	3060		

Well Type: EOR UIC Docket No: E12960.2 Date/Time to Plug: 02/18/2016 9:30 AM
 Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
 Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY CORP Phone: (620) 282-9034

Proposed Plugging Method: PER KCC DISTRICT 4 RULES AND REGULATIONS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
 Date/Time Plugging Completed: 02/18/2016 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

THIS WELL HAD A FAILED MIT. A CIBP HAS BEEN PREVIOUSLY SET AT 3295' AND CAPPED WITH CEMENT, AS WELL AS A CIBP AT 3040'--ALSO CAPPED WITH 4 SX'S CEMENT ON 12-10-2015. PERFORATE AT 1250', 900', AND 285'. RUN TUBING TO 1250' AND PUMP 35 SX'S COMMON CEMENT WITH 2% CC. PULL TUBING UP 600' AND WAIT 1 HOUR. TAGGED CEMENT AT APPROX. 1050' WITH SWAB BAR. RUN TUBING BACK DOWN TO 875' AND PUMP 35 SX'S COMMON CEMENT WITH 2% CC, PULL TUBING TO 285' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. CAME BACK ON 2-23-2016 AND RAN 1" DOWN BACKSIDE OF 5.5" AND FILLED UP WITH 60 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3236	3240	CSG	
3132	3140	CSG	
3109	3113	CSG	
3076	3079	CSG	

No CC-UIC 4-7-16

Remarks: LOG TECH OF KS #8651. GLOBAL CEMENT #2583. GLOBAL CEMENT # 2544 ON 2-23-2016. FAILED MIT.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
 (TECHNICIAN)

1/54

Received
 KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION
 WICHITA, KS