

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21303-00-00
Spot: SESESW Sec/Twnshp/Rge: 19-22S-22W
336 feet from S Section Line, 3073 feet from E Section Line
Lease Name: MILLER Well #: 1
County: HODGEMAN Total Vertical Depth: 4651 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	4.5	1514		WITH 225 SX CMT
L1	3.5	4484	0	WITH 140 SX CMT
PROD	4.5	4653	0	WITH 125 SX CMT
SURF	8.625	315		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/09/2016 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 25 SX CMT & 100# HULLS. PULL TBG TO 1520' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/09/2016 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4433' & SPOT 25 SX CMT & 100# HULLS. PULL TBG TO 1550' & PUMPED 110 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4590	4596		
4578	4586		
4491	4495		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
MAR 22 2016
KCC DODGE CITY



Signed Michael Maier
(TECHNICIAN)

no
4-7-16

Received
KANSAS CORPORATION COMMISSION
MAR 31 2016
CONSERVATION DIVISION
WICHITA, KS