

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22268-00-00
Spot: W2E2NE Sec/Twnshp/Rge: 10-14S-21W
1340 feet from N Section Line, 960 feet from E Section Line
Lease Name: LTD Well #: 1-10
County: TREGO Total Vertical Depth: 4173 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4172		150 SX
SURF	8.625	212		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2016 8:30 AM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING NELSON OIL Phone: (785) 623-3290

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 13 sx gel and 400 # hulls.
DV Tool at 1667' w/180 sx cement.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2016 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

PBTD: 4024'. Ran tubing to 3850' and pumped 13 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 1745' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 775' and pumped 100 sx cement w/good returns. POOH. Hooked to braden head and pumped 5 sx cement at 250 psi. Filled casing w/15 sx cement.
GPS: 38.85221 -099.63602

Perfs:

Top	Bot	Thru	Comments
4070	4075		
4052	4058		
3996	4002		

Remarks: SWIFT CEMENTING TICKET # 31720

Plugged through: TBG

District: 04

Signed Ray A. Dinkel

(TECHNICIAN)

cm

MAR 15 2016

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 22 2016

CONSERVATION DIVISION
WICHITA, KS

200
4-7-16