

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-19068-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 20-31S-6E  
2960 feet from S Section Line, 4901 feet from E Section Line  
Lease Name: BURDEN UNIT TR 1 Well #: 3  
County: COWLEY Total Vertical Depth: 2941 feet

Operator License No.: 30169  
Op Name: DOUBLE "D" OIL COMPANY, INC.  
Address: 2009 JEAN CT  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	2.875	2200		
PROD	2.875	2940		50 SX
SURF	7	208		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/18/2016 8:00 AM  
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING  
Proposal Rcvd. from: DONALD BUTLER Company: DOUBLE D OIL CO Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS / CMT 50' ABOVE TOP PERF, CIRC 350'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/19/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 1960', DUMP BAILED 3 SXS CEMENT ON TOP OF SAND.  
RIH W/ 1 1/2" TBG @ 350', MCPHERSON DRILLING PUMPED 55 SXS 60/40 POZMIX %  
GEL, CEMENT DID NOT CIRCULATE. LAYED DOWN TUBING. 2-19-2016, TAGGED  
CEMENT @ 80', RIH W 1 1/2" TBG @ 78', MCPHERSON DRILLING PUMPED 8 SXS TO  
SURFACE. CEMENT CIRCUALTED. DANIELS CEMENT TICKET # 035574.

Perfs:

Top	Bot	Thru	Comments
2905	2929	CSG	
2015	2028	CSG	

Remarks: COMPLIANCE / 10 YEAR RULE

Plugged through: TBG

District: 02

Signed

*DUANE KRUEGER*  
(TECHNICIAN)

*no*  
*4-7-16*

Received  
KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION  
WICHITA, KS

*JK*