

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20900-00-00
Spot: SWSNW Sec/Twnshp/Rge: 21-26S-7E
1416 feet from S Section Line, 4502 feet from E Section Line
Lease Name: HENN Well #: 1
County: BUTLER Total Vertical Depth: 2836 feet

Operator License No.: 7228
Op Name: BRICKLEY, DONALD DBA D & J INVES
Address: 107 SE BLUESTEM RD. PO BOX 107
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2836		75 SX
SURF	8.625	198		75 SX
SURF	8.625	200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2015 12:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: ANDY BRICKLEY Company: D & J INVESTMENTS Phone: (316) 323-4623

Proposed Plugging Method: AS PER KCC RULES & REGS /SAND @ 2720' W/4 SXS CEMENT, CIRC 250'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 10/12/2015 12:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, TAGGED TD @ 2780', POOH W/WIRELINE. SANDED WELL BACK @ 2710'. SDON. 10/19/2015, DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. RIH ON WIRELINE, CUT CASING @ 1,000'. SDON. 10/20/2015, LAYED DOWN 1,000' 4 1/2" CASING. RIH W/4 1/2" DUMP BAILOR & BAILED HOLE @ 250', CNC POURED 4 1/2 YDS (90 SXS) OIL SLURRY LESS 10% SAND TO SURFACE. P&A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2772	2788		CSG

Remarks: COMPLIANCE 10/ YEAR RULE

Plugged through: TBG

District: 02 Signed: DUANE KRUEGER (TECHNICIAN) no 4-7-16

Received
KANSAS CORPORATION COMMISSION
Form CP-2/3
MAR 24 2016
CONSERVATION DIVISION
WICHITA, KS

JK