

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-21840-00-00  
Spot: SWSWNWSW Sec/Twnshp/Rge: 21-26S-7E  
1535 feet from S Section Line, 5046 feet from E Section Line  
Lease Name: HENN ESTATE Well #: 3  
County: BUTLER Total Vertical Depth: 2800 feet

Operator License No.: 7228  
Op Name: BRICKLEY, DONALD DBA D & J INVES  
Address: 107 SE BLUESTEM RD. PO BOX 107  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2785		
PROD	4.5	2800		75 SX
SURF	8.62	176		75 SX
SURF	8.625	202		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2015 12:00 AM  
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL  
Proposal Rcvd. from: ANDY BRICKLEY Company: D&J INVESTMENTS Phone: (316) 323-4623

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 2700 W/4 SXS CEMENT, CIRC 250'-0'.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/12/2015 12:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCULATING VARIOUS BRIDGES @ 500', & 650', CIRCULATED TBG @ 2010', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 1421'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 250'-251'. RIH W/TBG @ 260', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS CLASS A COMMON TO SURFACE. LAYED DOWN TUBING. SWEDGED INTO 4.5', & PUMPED 45 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. P&A COMPLETE. CONSOLIDATED OIL WELL SERVICES CEMENT TICKET #48398.

Perfs:

Top	Bot	Thru	Comments
2750	2800		CSG

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAR 24 2016 CP-2/3

CONSERVATION DIVISION  
WICHITA, KS