

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-20517-00-00
Spot: W2SWSW Sec/Twnshp/Rge: 19-21S-19W
660 feet from S Section Line, 330 feet from W Section Line
Lease Name: BRYANT GLENN Well #: 1-19
County: PAWNEE Total Vertical Depth: 2315 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2100		WITH 2 SX CMT
PROD	4.5	2313	0	WITH 100 SX CMT
SURF	7	899		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/15/2016 9:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 2100' WITH 2 SX CMT. PERFORATE 4 HOLES AT 1194'. INJECTION RATE WITH WATER. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/15/2016 2:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 2100' WITH 2 SX CMT. PERFORATE 4 HOLES AT 1194'. BREAK CIRCULATION WITH WATER. PUMP 240 SX CMT AT 50 PSI. STOPPED WORK. PUMPED ADDITIONAL 30 SX CMT AT 400 PSI. PUMPED 25 SX CMT DOWN 7" X 4 1/2" ANNULUS. PRESSURED TO 250 PSI. BOTH 4 1/2" CASING & ANNULUS STANDING FULL WHEN FINISHED CEMENTING.

Perfs:

Top	Bot	Thru	Comments
2202	2208		
2146	2159		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENTING.

Plugged through: CSG

District: 01

Signed

Ken Scofield
517

(TECHNICIAN)

RECEIVED
MAR 22 2016
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
Form CP-2/3

MAR 31 2016

CONSERVATION DIVISION
WICHITA, KS

no
4-7-16