

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19476-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 26-31S-5E
1038 feet from S Section Line, 2289 feet from E Section Line
Lease Name: SU-STABECK Well #: 3
County: COWLEY Total Vertical Depth: 2334 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2334		75 SX
SURF	8.625	201		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2016 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 2250' W/ 5 SXS CIRC. 350'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/16/2016 4:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2250', DUMP BAILED 5 SXS CEMENT ON TOP OF SAND. TAGGED BOTTOM PLUG @ 2228'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLE @ 360'-361'. RIH W/ TBG @ 360', GRESSEL OILFIELD ESTABLISHED CIRCULATION, MIXED & PUMPED 160 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #37447.

Perfs:

Top	Bot	Thru	Comments
2301	2313	CSG	

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

no
4-7-16

Received
KANSAS CORPORATION COMMISSION
Form CP-2/3
MAR 24 2016
CONSERVATION DIVISION
WICHITA, KS

1/2