

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19478-00-00
Spot: SENESE Sec/Twnshp/Rge: 26-31S-5E
1721 feet from S Section Line, 369 feet from E Section Line
Lease Name: SU-STABECK Well #: 5
County: COWLEY Total Vertical Depth: 2312 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2301		100 SX
SURF	8.625	201		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2016 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 2250' W/5 SXS CIRC. 350'-0'

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/16/2016 10:45 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2250', DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. TAGGED BOTTOM PLUG @ 2232'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLE @ 360'-361'. RIH W/ TBG @ 350', GRESSEL OILFIELD ESTABLISHED CIRCUALTION, MIXED & PUMPED 175 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #37445.

Perfs:

Top	Bot	Thru	Comments
2301	2312		CSG

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

no
4-7-16

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 24 2016

CONSERVATION DIVISION
WICHITA, KS

JK