

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19479-00-00

Spot: NWSESE

Sec/Twnshp/Rge: 26-31S-5E

1069 feet from S Section Line, 1055 feet from E Section Line

Lease Name: SU-STABECK

Well #: 6

County: COWLEY

Total Vertical Depth: 2303 feet

Operator License No.: 4419

Op Name: BEAR PETROLEUM, LLC

Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2296		100 SX
SURF	8.625	200		100 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/12/2016 8:00 AM

Plug Co. License No.: 3004

Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC

Proposal Rcvd. from: JOE BURNETT

Company: BEAR PETROLEUM

Phone: (316) 524-1225

Proposed
Plugging
Method:

AS PER KCC RULES & REGS / SAND 2 2245' W/ 4 SXS CIRC 350'-0'.

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: PARTIAL

Date/Time Plugging Completed: 02/16/2016 11:45 AM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2240', DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. TAGGED BOTTOM PLUG @ 2225'. RIH ON WIRELINE, PERFORATED SQUEZE HOLE @ 360'-361'. RIH W/TBG @ 360', GRESSEL OILFIELD ESTABLISHED CIRCULATION, MIXED & PUMPED 155 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #37446.

Perfs:

Top	Bot	Thru	Comments
2296	2303	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION
WICHITA, KS