

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-22238-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 3-35S-2E  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease Name: YUST Well #: 2  
County: SUMNER Total Vertical Depth: 3154 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		820		
CIBP		2810		
PROD	5.5	3136		170 SX
SURF	8.625	255		170 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2016 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/28/2016 1:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 745' DUMP BAIL 2 SX FOR CAP. LOADED CASING AND PRESSURED UP TO 500 PSI. CASING STOOD FULL. PERFORATED 5.5" AT 305' AND RAN IN WITH TUBING TO 315' AND CIRCULATE 45 SX TO SURFACE W/60/40 POS MIX USING COPELAND ACID AND CEMENT, CAME BACK AND TOPPED OFF CASING WITH 10 SX. 55 SX TOTAL ON TICKET #37441. PLUG JOB COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2774	2780	TBG	
795	800	TBG	

Remarks: OPERATOR PLUGGED WELL AFTER DENIED TA APPLICATION.

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*Daniel P. Fox*

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION  
WICHITA, KS

*220*  
*4-7-16*

Form CP-2/3