

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-10273-00-00  
Spot: SWNW Sec/Twnshp/Rge: 2-24S-21W  
3330 feet from S Section Line, 4628 feet from E Section Line  
Lease Name: REGNIER Well #: 1  
County: HODGEMAN Total Vertical Depth: 4774 feet

Operator License No.: 31093  
Op Name: BECKER OIL CORPORATION  
Address: PO BOX 1150  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4770	0	WITH 125 SX CMT
SURF	8.625	295		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2016 8:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: DOUG BROWN Company: BECKER OIL Phone: (620) 287-4724

Proposed Plugging Method: PUMP 50 SX CMT WITH HULLS. PERFORATE AT 1490' & PUMP 50 SX CMT WITH 3% CC. PULL TBG & LET SET OVERNIGHT. PRESSURE CASING. IF IT TESTS OK PERFORATE AT 660' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/14/2016 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

\*\*THERE IS A 4 1/2" LINER IN THE HOLE BUT THERE ARE NO RECORDS INDICATING THE DEPTH OF IT.\*\* 3/11/16: PERFORATED AT 1490'. RAN TBG TO 4616' & PUMPED 50 SX CMT WITH 100# HULLS. PULLED TBG TO 1318' & BROKE CIRCULATION WITH WATER. PUMPED 50 SX COMMON CMT WITH 3% CC. PULLED TBG & SDFW. 3/14/16: TAGGED CMT AT 1075'. PRESSURED TESTED THE CASING TO 300# & HELD. PERFORATED AT 660'. TIED ONTO THE 4 1/2" & CIRCULATED 80 SX CMT UP THE 4 1/2" X 5 1/2: ANNULUS, PRESSURING TO 1000#. CLOSED THE 4 1/2" X 5 1/2" ANNULUS VALVE & TIED ONTO THE 5 1/2" X 8 5/8" ANNULUS PUMPING 90 SX CMT, PRESSURING TO 900#.

Perfs:

Top	Bot	Thru	Comments
4617	4623		


Remarks: USED COMMON CMT W/3% CC & 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED  
MAR 22 2016  
KCC DODGE CITY

Signed

  
JA

(TECHNICIAN)  
KCC WICHITA

APR 01 2016

RECEIVED

Form CP-2/3

220  
4-6-16