

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24309-00-00
Spot: SESWNESW Sec/Twnshp/Rge: 10-17S-21W
1492 feet from S Section Line, 3328 feet from E Section Line
Lease Name: SWARTS A Well #: 1-10
County: NESS Total Vertical Depth: 4250 feet

Operator License No.: 33993
Op Name: QUEST ENERGY LLC
Address: 2732 N REESE RD
BROOKVILLE, KS 67425

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1460		WITH 350 SX CMT
PROD	5.5	4247	0	WITH 150 SX CMT
SURF	8.625	212		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2016 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: TRACY HYNES Company: QUEST ENERGY LLC Phone: (785) 283-4249

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS WITH 5 SX CMT. RUN TBG TO 1500' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. PUMP 50 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2016 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 3600' & SPOT 10 SX SAND. WAIT 1 HOUR & TAG SAND AT 4077'.
PULL TBG TO 4050' & PUMP 10 SX CMT. PULL TBG TO 1500' & PUMP 165 SX CMT.
CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT.
TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4234	4236		
4124	4126		
4122	4126		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier

JA

(TECHNICIAN)

KCC WICHITA

RECEIVED
MAR 29 2016
KCC DODGE CITY

MD

APR 01 2016

RECEIVED

Form CP-2/3

no
4-7-16