

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-119-21082-00-01  
Spot: W2SWSESW Sec/Twnshp/Rge: 18-33S-29W  
330 feet from S Section Line, 1550 feet from W Section Line  
Lease Name: BURMEISTER Well #: 1-18  
County: MEADE Total Vertical Depth: 6225 feet

Operator License No.: 34242  
Op Name: OOLITE ENERGY CORP  
Address: PO BOX 9398  
AMARILLO, TX 79105

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6090		
PROD	5.5	6223	3004	WITH 245 SX CMT
SURF	8.625	1551		WITH 500 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/10/2016 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 251-1881

Proposed Plugging Method: CIBP @ 6000' WITH 5 SX CMT OR PUMP CMT. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/10/2016 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

PUMP BOTTOM WITH 25 SX CMT & 300# HULLS. 1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6172	6174		
6154	6156		
6148	6149		
6141	6142		
6133	6134		
6122	6123		
6111	6112		
6105	6106		
6060	6061		
6056	6057		
6053	6054		
6051	6052		
6049	6050		

Remarks: USED CLASS A CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
MAR 14 2016  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION

MAR 31 2016

CONSERVATION DIVISION  
WICHITA, KS

NO  
4-7-16