

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-129-10365-00-00  
Spot: NW Sec/Twnshp/Rge: 5-35S-42W  
3959 feet from S Section Line, 3966 feet from E Section Line  
Lease Name: PAT MAC Well #: 1-5  
County: MORTON Total Vertical Depth: 3132 feet

Operator License No.: 32638  
Op Name: NADEL AND GUSSMAN LLC  
Address: 15 E 5TH ST STE 3300  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2450		WITH 2 SX CMT
PROD	5.5	3131	628	WITH 200 SX CMT
SURF	8.625	604		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/15/2016 1:00 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 251-1881

Proposed Plugging Method: CUT TBG ABOVE FREE POINT. 25 SX CMT WITH HULLS AT TOP OF STUB. BLOW COLLAR AT +/- 1360'. RUN TBG TO +/- 1360' & SPOT 40 SX CMT. CUT CASING BELOW 604' & SPOT 50 SX CMT. 10 SX CMT AT 40'.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/16/2016 2:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

3/15/16: CUT TBG AT 2600'. SET CIBP @ 2450' WITH 2 SX CMT. CASING LEAK AT 1100'-1200'. BLEW COLLAR AT 1371'. RAN TBG TO 1371' & SPOT 40 SX CMT. CUT CASING AT 628'. SPOT 50 SX CMT. HAD CIRCULATION BUT WENT ON VACUUM. WAITED 2 HOURS. TOC BELOW 604'. 3/16/16: RAN TBG TO 630' & PUMPED 200# HULLS WITH MUD. SPOT 50 SX CMT AT 630'. TAGGED TOC @ 493'. PUMP 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
2970	2987		
2937	2942		
2909	2922		
2897	2904		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed [Signature]

SA (TECHNICIAN)

RECEIVED  
MAR 22 2016  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
Form CP-2/3  
MAR 31 2016  
CONSERVATION DIVISION  
WICHITA, KS