

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23971-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 31-34S-3E
425 feet from S Section Line, 2260 feet from E Section Line
Lease Name: MARRS Well #: 1 A
County: COWLEY Total Vertical Depth: 1587 feet

Operator License No.: 34934
Op Name: MARRS, MARILYNN W. REVOCABLE T
Address: 28784 11TH RD
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1565		80 SX
SURF	8.625	305		170 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/15/2016 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: LARRY ANSTINE Company: AAS OIL Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS / TBG TO BOTTOM SPOT BOTTOM, CIRC. 350'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 02/15/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 1500', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 3% CC 50# HULLS & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1285'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 360'-361'. RIH W/ TBG @ 360', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 135 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING. CEMENT CIRCULATED. CEMENT TICKET #51154.

Perfs:

Top	Bot	Thru	Comments
1504	1515	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 24 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
4-9-16

134