

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-115-01308-00-00
Spot: SESWNE Sec/Twnshp/Rge: 15-19S-4E
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: RUSSELL A Well #: 1
County: MARION Total Vertical Depth: 2332 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2326		100 SX
SURF	8.625	150		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2016 12:00 PM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD L. DINKEL Company: TERRY MORRIS Phone: (785) 639-5415

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2016 3:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

2/29/2016 1) SANDED OFF PERFORATIONS TO 2172' (TAGGED W/ DUMP BAILER) AND CAPPED W/5 SKS CEMENT. 2) GEMINI WIRELINE PERFORATED AT 250'.
3/1/2016 1) RAN IN HOLE W/TUBING TO APPROX 250' AND PUMPED 150 SKS OF 60/40 4% CEMENT W/ NO ADDITIVES. CEMENT CIRCULATED TO SURFACE UP 5.5" CASING AND BACKSIDE. 2) PULLED TUBING OUT, TOPPED OFF 5.5" CASING W/30 SKS CEMENT. BACKSIDE REMAINED FULL. 3/7/2016 1) TAGGED CEMENT PLUG IN 5.5" CASING AT APPROX. 85'. BACKSIDE DOWN 30' (NO FLUID IN HOLE). 2) WELL TOPPED OFF BACK TO SURFACE W/ APPROX. 1.5 YDS CEMENT SLURRY MIX POURED FROM TOP.

Perfs:

Top	Bot	Thru	Comments
2312	2322	CSG	

Remarks: CEMENTING COMPLETED BY GLOBAL CEMENTING LLC. RUSSELL, KS. TICKET #2547

Plugged through: TBG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 31 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

NO
4-7-16

✓ SK