

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-20888-00-01  
Spot: SWSESWNE Sec/Twnshp/Rge: 31-6S-23W  
2929 feet from S Section Line, 1676 feet from E Section Line  
Lease Name: ELLIOTT Well #: 2 WIW  
County: GRAHAM Total Vertical Depth: 3951 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3942		175 SX
SURF	8.625	305		275 SX

Well Type: EOR UIC Docket No: E27475.1 Date/Time to Plug: 03/11/2016 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Revd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Port Collar at 2183' w/375 sx cement.  
Injection zone perforations: 3887' - 3893'.  
Packer at 3840'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/11/2016 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Failed MIT. Tubing parted at 2991'. Ran tubing to 2961'. Hurricane Services pumped 150 sx cement. Pulled tubing to 2201' and pumped 125 sx cement w/250 # hulls. Pulled tubing to 995' and pumped 80 sx cement w/200 # hulls. Cement circulated. PTOH. Topped 5 1/2" casing off w/25 sx cement. Hooked up to backside and pumped 25 sx cement. Maximum pressure 300 psi. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3887	3893		

Remarks: 849' OF 2 3/8" SEALTITE TUBING W/LOCKSET PACKER AT 3840'. HURRICANE SERVICES TICKET # 100628

Plugged through: TBG

District: 04

Signed Richard Williams

(TECHNICIAN)  
Received  
KANSAS CORPORATION COMMISSION

CM

MAR 15 2016

MAR 22 2016  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3  
no  
cc-uic  
4-7-16