

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00790-00-00
Spot: SESENW Sec/Twnshp/Rge: 28-30S-8W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: A R CARRICK B Well #: 1
County: KINGMAN Total Vertical Depth: 4377 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4374	100	100 SX
SURF	8.625	200	135	135 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/14/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (405) 203-4936

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/17/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RAN TUBING INTO 4240' SPOTTED 35 SX CEMENT WITH 150 LBS HULLS & 3% CC. TAGGED TOC @ 3670'. WELL HAD POOR BOY SQUEEZE FROM TOP, NIPPLES ON SURFACE CASING WERE HALF FULL OF CEMENT, ALSO CASING LEAK AT 750' HAD BEEN PRODUCING UNDER PACKER. PERFORATED @ 1350' - 900' & 250'. RAN TUBING INTO 1350' SPOTTED 35 SX CLASS A CEMENT W/ 100 LBS HULLS & 3% CC, WAITED 2 HOURS TAGGED TOC @ 1290'. TUBING TO 900' 35 SX CEMENT, TUBING TO 750' TO COVER CASING LEAK SPOTTED 35 SX CEMENT, TUBING TO 250' AND CIRCULATED TO SURFACE WITH 35 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4297	4337		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THESE JOB ALSO, CLASS A CEMENT WAS USED IN THIS PLUGGING. PAST 10 YEAR TA.

Plugged through: TBG

District: 02

Signed B. J. Hope

KCC WICANTA

APR 05 2016

RECEIVED

Form CP-2/3

710
4-7-16

✓ SK