

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-01196-00-00
Spot: SWNESE Sec/Twnshp/Rge: 27-30S-8W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: C J BOYLE E (WSU 42 2) Well #: 2
County: KINGMAN Total Vertical Depth: 4435 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4434		200 SX
SURF	8.625	194		250 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/28/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (405) 203-4936

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/28/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RAN TUBING INTO 4240' SPOTTED 35 SX OF CEMENT W/150 LBS HULLS & 3% CC. TAGGED TOC @ 3933'. CASING LEAK AT 850'. PERFORATED @ 1350', 850' & 250'. RAN TUBING IN TO 1350' SPOTTED 35 SX CLASS A CEMENT W/150 LBS HULLS 3% CC, WAITED 2 HOURS TAGGED @ 1235'. TUBING TO 850' SPOTTED 50 SX CEMENT 50 LBS HULLS & 3% CC. RAN TUBING TO 250' AND CIRCUALTED TO SURFACE WITH 210 SX OF CEMENT. 3/28/16 CUT HEAD OFF AND ONE INCHED BETWEEN SURFACE & CASING ANOTHER 90 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4326	4338		
4269	4320		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR PLUGGING. CLASSA USED. PAST 10 YEAR TA.

Plugged through: TBG

District: 02

Signed B. J. Hope

(TECHNICIAN)
KCC WICHITA

APR 05 2016

RECEIVED

Form CP-2/3

70
4-7-16

SK