

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00097-00-00
Spot: SENESW Sec/Twnshp/Rge: 28-30S-8W
1650 feet from S Section Line, 2310 feet from W Section Line
Lease Name: TJADEN I Well #: 1
County: KINGMAN Total Vertical Depth: 4395 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4390		150 SX
PROD	5	4395		50 SX
SURF	8.625	160		150 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/16/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 425-1000

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/23/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RAN INTO 880' STACKED OUT SAND LINE WITH BAILER ON IT. RAN TUBING IN WITH BIT AND CONNECTED TO SWIVEL DRILL OUT 108' OF BRIDGE. RAN TUBING TO 4240' SPOTTED 35 SX CLASS A CEMENT W/150 LBS OF HULLS & 3% CC. TAGGED TOC @ 3850'. PERFORATED AT 1350', 880' & 250'. RAN TUBING TO 1350' SPOTTED 35 SX CEMENT W/ 150 LBS HULLS & 3% CC, WAITED 2 HOURS TAGGED CEMENT @ 890', RAN TUBING TO 880' SPOTTED 50 SX CEMENT W/150 LBS HULLS 3% CC. RAN TUBING TO 250' CIRCUALTED TO SURFACE WITH 60 SX CEMENT. CUT HEAD OFF CHECK BACKSIDE FOR CEMENT. CEMENT WAS STILL AT SURFACE NEXT AM.

Perfs:

Top	Bot	Thru	Comments
4332	4336		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS PLUG JOB, CLASS A CEMENT. PAST TEN YEAR TA.

Plugged through: TBG

District: 02

Signed B. J. Hope

KCC WICHIITA

APR 05 2016

RECEIVED

Form CP-2/3

710
4-7-16

SLC