

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-20977-00-00  
Spot: N2SWSWSE Sec/Twnshp/Rge: 5-25S-5W  
580 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: TONN Well #: 2  
County: RENO Total Vertical Depth: 3595 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3595		
PROD	5.5	3595	2300	250 SX
SURF	8.5	458		175 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/26/2016 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: TRACY BLACK Company: \_\_\_\_\_ Phone: (316) 215-1873

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/26/2016 4:00 PM KCC Agent: B. J. HOPE

**Actual Plugging Report:**

SANDED BACK TO 3402' CAPPED WITH 5 SK CEMENT ON TOP. CUT CASING PIPE OFF @ 2300' PULLED CASING TO 772' SPOTTED 35 SX CEMENT. PULLED CASING TO 456' CIRCUALTED TO SURFACE WITH 145 SX CEMENT. FIRST 100 SX OF CEMENT WAS CLASS A WITH 3% CC, NEXT 80 SX CEMENT WAS 60/40 4%. 1/27/16 CEMENT FELL BACK 25' ADDED 5 SX OF CEMENT TO TOP OFF.

**Perfs:**

Top	Bot	Thru	Comments
3467	3471		

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, TICKET #43578.

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)  
Received  
KANSAS CORPORATION COMMISSION

NO  
4-7-16

MAR 31 2016

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

✓