

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-22994-00-00
Spot: SESENW Sec/Twnshp/Rge: 24-16S-26W
2971 feet from S Section Line, 2949 feet from E Section Line
Lease Name: MCKINNIS B Well #: 1
County: NESS Total Vertical Depth: 4580 feet

Operator License No.: 33984
Op Name: LUTZ, SCOTT T. TRUST
Address: PO BOX 1766 PO BOX 1766
FAYETTEVILLE, AR 72702

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4578	0	WITH 200 SX CMT
SURF	8.625	345		WITH 230 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2016 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KENNY RUPP Company: NORTH FORK SERVICES Phone: (785) 798-5260

Proposed Plugging Method: RUN TBG TO 4400' & PUMP 50 SX CMT & 200# HULLS. PULL TBG TO 2000' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/21/2016 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

HAD PUMPED 350 SX CMT DOWN BACKSIDE & FOUND CMT AT 2210'. RAN TBG TO 4400' & PUMPED 50 SX CMT & 150# HULLS. PULLED TBG TO 2000' & PUMPED 130 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4515	4580		
4416	4480		

Remarks: **COMPLIANCE ISSUE: DENIED TA NEED FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
MAR 22 2016
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
Form CP-293
MAR 31 2016
CONSERVATION DIVISION
WICHITA, KS